

Carnation Drive Culverts (Pipes)

Construction Planned

Project Description: The City's bridge rehabilitation contractor, *Concrete General, Inc.*, will repair the Carnation Drive culverts (pipes). Construction is scheduled to begin during the week of July 6 and will continue for three weeks, weather permitting.

These two pipes are each approximately 96-inch diameter corrugated metal pipes (CMP). The CMP structures were installed in 1969 and the pipe inverts (bottoms) are severely corroded. The proposed repairs will involve removing portions of the metal pipe, filling the voids along the bottom and pouring a new concrete invert. Impacts during construction include on-street parking restrictions and construction noise. If necessary, "No Parking" signs will be posted 48 hours in advance. Trees growing on top of the structure were previously removed.

Purpose: As part of Rockville's Bridge Rehabilitation program, the Department of Public Works (DPW) is repairing bridges and small structures within public rights-of-way. Inspections of the 39 City-owned small structures (culverts) have been completed. This program meets the Mayor and Council's goal for sustainable infrastructure. The repairs are prioritized based on structural improvements recommended in inspection reports.

Location: Carnation Drive east of Aster Boulevard near the stormwater management facility.

Timeline: Construction is scheduled to start during the week of July 6. Work will take place during the day from 7 a.m. to 5 p.m.

Cost: \$150,000 (estimated construction cost)

Contact: **John W. Hollida**, City of Rockville Project Manager, at 240-314-8526 or jhollida@rockvillemd.gov

Rocio Snowdy, City of Rockville Neighborhood Resources Coordinator, 240-314-8345 or rsnowdy@rockvillemd.gov

