

# Monroe Street Culverts (Pipes)

## Construction Planned

**Project Description:** The City's bridge rehabilitation contractor, *Concrete General, Inc.*, will be constructing repairs to the Monroe Street culverts (pipes). Construction is scheduled to begin during the week of Sept. 30 and will continue for six weeks, weather permitting.

These two pipes are each approximately 42-inch diameter corrugated metal pipes (CMP). The structures were installed in 1960 and the pipe inverts (bottoms) are severely corroded. The proposed construction consists of the following repairs: removing portions of the metal pipe, filling the voids along the bottom and pouring a new concrete invert. Impacts during construction include on-street parking restrictions and construction noise. If necessary, "No Parking" signs will be posted 48 hours in advance.

**Purpose:** As part of Rockville's Bridge Rehabilitation program, the Department of Public Works (DPW) will be repairing bridges and small structures within public rights-of-way. Inspections of the 39 City-owned small structures (culverts) have been completed. This program meets the Mayor and Council's goal for a sustainable infrastructure. The repairs are prioritized based on structural improvements recommended in inspection reports.

**Location:** Intersection of Monroe Street and Cabin John Parkway

**Timeline:** Construction is scheduled to start during the week of Sept. 30. Work will take place during the day from 7 a.m. to 5 p.m.

**Cost:** \$35,000 (estimated construction cost)

**Contact:** **John W. Hollida**, City of Rockville Project Manager, at 240-314-8526 or [jhollida@rockvillemd.gov](mailto:jhollida@rockvillemd.gov)

**Rocio Snowdy**, City of Rockville Neighborhood Resources Coordinator, 240-314-8345 or [rsnowdy@rockvillemd.gov](mailto:rsnowdy@rockvillemd.gov)

