



**CITY OF ROCKVILLE
ROCKVILLE, MARYLAND
ADDENDUM #1**

**INVITATION FOR BID #56-11
REPLACE AND REPAIR FRAMING TIMBERS AND ASSOCIATED ROOFING FOR
THE HAY BARN AT THE KING FARM FARMSTEAD**

Contractors submitting proposals for the above named project shall take note of the following changes, additions, deletions and clarifications in the Bid Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Bid Documents and all shall be taken into consideration and be included in the Contractor's Bid Proposal.

Bid Due Date: May 24, 2011 @2 p.m.

Please note the following clarifications related to the above referenced project:

1. On page 22, under item #3, MILLING, two (2) additional sister rafters, 2 inches by 7 inches by 14 feet long, are to be installed between the P2 and the center ridge of the barn, one in area B and one in area C. This increases the number of Sister Rafters from eight (8) each to ten (10) each. See revised Estimated No. 2 Grade Oak Cut List below:

REVISED ESTIMATED No. 2 GRADE OAK CUT LIST				
DESCRIPTION*	Quantity	Height	Width	Length
Post B4-P2	1	6"	6"	16'
Built-up Beam P2 B2-B4	8	2"	8"	16'
Braces B3-P2	3	2"	6"	8'
Sister Rafters Bays B & C	10	2"	7"	14'

2. On page 23, under item #5, ROOFING, please disregard the second bullet, *Loose roofing to be refastened at the P1 eave in bay area*. The work has already been completed and should not be included in the total bid price.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.

Issued by:
Mary Heckhaus, Buyer II

Acknowledge receipt of this Addendum #1 by signing below and returning two (2) copies of the addendum with your bid proposal or acknowledging directly in the space provided on the bid proposal form.

NAME OF FIRM: _____

AUTHORIZED SIGNATURE: _____